

Questions Regarding RFP for Jockey Alley & Parking Lot #2

Q. Can you tell us what the pavement thickness of the alley and parking lot are or an estimated thickness of what you think it may be?

A. The only area that we can be sure of is the area in the southeast corner of the parking lot. When the round-about was constructed that area was found to have between 9"-12" of asphalt. The driving lane in that area had 6" of concrete underneath 3"-6" asphalt. The rest of the project will require borings in order to be sure of the existing cross section.

Q. Does the City have the conceptual layout amenities prioritized in regard to which will be most likely included in the project.

A. The dumpster enclosures and lighting are high priorities. The bus shelters will not be included in the final design. All other amenities will be prioritized prior to final design once the awarded consultant provides a rough cost estimate for those amenities.