



THE CITY OF
MT. PLEASANT, MICHIGAN

CITY HALL

320 W. Broadway • 48858-2312
(989) 779-5300
(989) 773-4691 fax

PUBLIC SAFETY

804 E. High • 48858-3595
(989) 779-5100
(989) 773-4020 fax

PUBLIC WORKS

1303 N. Franklin • 48858-4682
(989) 779-5400
(989) 772-6250 fax

PRE-BID ADDENDUM NO. 2

Project Bid: 2013 Parking Lot #2 Improvements

Bid Date: March 5, 2013

Time: 1:30 p.m.

Opening: Office of the City Clerk
City Hall
320 West Broadway St.
Mt. Pleasant, MI 48858

Addendum Issued By: Division of Public Works

Date Issued: February 28, 2013

Intent: 1. Answer electrical questions.

Proposal Form Revisions:

Change the quantity of Bid Item 55 – Light Standard Shaft and Luminaire, 24 foot from a quantity of 5 to a quantity of 4.

Change the quantity of Bid Item 57 – Light Std Fdn, Tall from a quantity of 5 to a quantity of 4.

Answers to Electrical Questions:

1. Does all of the wiring for all lighting, receptacle, and car charging station circuits need to be #6 wire? **Wire size can be reduced from #6 to #8 for all receptacle circuits. Pole lighting circuits X106 and X107 can be reduced from #6 to #8 wire. Pole lighting circuit X104 can be reduced from #6 to #10 wire.**
2. Will there be any in ground pull boxes required on the project? Please provide a detail and a quantity if they are required. **No pull boxes are required due to lot size.**
3. Please provide details for the Light Std Fdn, Short and Light Std Fdn, Tall. **The detail for Light Standards is on sheet C6.0.**
4. I count (4) Type S2 Light Poles on drawing E1. Bid item 55 Light Standard Shaft and Luminaire, 24 Foot has a quantity of (5). Will the installation of Type S2 light poles be paid for with Bid Item 55? What is the correct quantity of poles? **The correct Quantity is (4). Please change the quantity on the bid form. Per the ELECTRICAL AND LIGHTING Special Provision, bid Item 55 will pay for the installation of the Owner provided light poles and luminaires.**
5. Will the installation of Type S1 light poles be paid for with Bid Item 54 Light Standard Shaft and Luminaire, 15 Foot? **Per the ELECTRICAL AND LIGHTING Special Provision, bid Item 54 will pay for the installation of the Owner provided light poles and luminaires.**
6. The car charging station specification says to install an empty 1" conduit from the charging station to the control panel. Where will the control panel be located? Who is supplying the control panel? Who is installing it? **The conduit is for a telecommunications line. The intent is to run the conduit from the car charging station to the same area as the new Service Panel.**
7. There is a "Carnival Panel" shown on drawing E1. Who is supplying this panel? Who is installing it? Is there are specification / details for this panel? **This item is to be furnished and installed by the Contractor. Provide 2P60A non-fused Nema 3R disconnect switch mounted on a unistrut structure to support disconnect switch.**