



THE CITY OF  
MT. PLEASANT, MICHIGAN

---

**CITY HALL**

320 W. Broadway • 48858-2312  
(989) 779-5300  
(989) 773-4691 fax

**PUBLIC SAFETY**

804 E. High • 48858-3595  
(989) 779-5100  
(989) 773-4020 fax

**PUBLIC WORKS**

1303 N. Franklin • 48858-4682  
(989) 779-5400  
(989) 772-6250 fax

---

**PRE-BID ADDENDUM NO. 1**

---

Project Bid: 2013 Sewer Relining

Bid Date: March 26, 2013  
Time: 1:30 p.m.

Opening: Office of the City Clerk  
City Hall  
320 West Broadway St.  
Mt. Pleasant, MI 48858

Addendum Issued By: Division of Public Works

Date Issued: March 1, 2013

Intent: 1. To correct the start and completion dates

Bid Proposal: No change

Special Conditions: Revised and Attached

[FORM163]

**2013 SEWER RELINING PROJECT  
SPECIAL CONDITIONS**

**SCOPE:**

This project involves the relining of sanitary sewer mains in accordance with the specifications. All work required to complete the relining, reestablish the services, and return the main to full service shall be included in the unit prices in the proposal.

**TIME CONSTRAINT:**

The Contractor shall complete this work between May 6, 2013, and July 3, 2013. Chippewa Street between West Grand and East Drive is scheduled to be overlaid in the summer of 2013. Therefore, relining work shall be coordinated with the Chippewa Street work so that the sanitary sewer can be relined prior to Chippewa Street being paved. All work on this project shall be completed by July 3, 2013. Liquidated damages at the rate of \$300.00 per day will be assessed for each day the project is not completed beginning on July 3, 2013.

**SCHEDULE:**

The Contractor shall notify the Engineer regarding their schedule for performing the work at least a week prior to the work beginning. The Contractor shall give the Water Supervisor a list of hydrants proposed to be used for the project prior to beginning any portion of the project. Upon completion of the project, the Contractor shall give the Water Supervisor a list of hydrants actually used during the project.

**SEWER SERVICE:**

The sewers to be relined on pages 5, 6, and 12 of the location map serve several businesses. The Contractor shall coordinate with the businesses regarding the best time of day to reline the sewer main. The Contractor shall schedule all activities to minimize the impact of the sewer service interruption.

**PIPE THICKNESS:**

The minimum pipe thickness for the various pipes shall be:

- 8" CIPP – 6 mm
- 10" CIPP – 7.5 mm
- 12" CIPP – 7.5 mm
- 15" CIPP – 10.5 mm

**STANDARD CONSTRUCTION SPECIFICATIONS:**

The City of Mt. Pleasant's Standard Construction Specifications dated 2007 must be followed for construction on this project. They are available on the City's webpage at <http://www.mt-pleasant.org/docs/dept/engineering/genspec07.pdf>