



THE CITY OF MT. PLEASANT, MICHIGAN

CITY HALL
320 W. Broadway • 48858-2312
(989) 779-5300
(989) 773-4691 fax

PUBLIC SAFETY
804 E. High • 48858-3595
(989) 779-5100
(989) 773-4020 fax

PUBLIC WORKS
1303 N. Franklin • 48858-4682
(989) 779-5400
(989) 772-6250 fax

PRE-BID ADDENDUM NO. 1

Project Bid: Mission Street Connector #1

Bid Date: July 16, 2013

Time: 1:30 p.m.

Opening: Office of the City Clerk
City Hall
320 West Broadway St.
Mt. Pleasant, MI 48858

Addendum Issued By: Division of Public Works

Date Issued: July __, 2013

Intent:

1. Clarify questions that have been asked.
2. Add Special Provisions.
3. Make adjustments to the pay items.

Bid Proposal: Revised and attached

Special Provision: Revised and attached

Clarifications:

1. Is it the intent to crush the existing asphalt and use that for the agg base and grade it to the curb? **Yes. The existing asphalt in the existing main parking lot is to be crushed and shaped using the HMA Base Crushing and Shaping pay item. This is for the Connector Road only.**
2. At the CMU entrance and Papa John's, are we reusing that material also? **At Papa John's, the pavement is being removed using the Pavt, Rem pay item that is a standard MDOT pay item. It is the intent to utilize the existing base material where there is existing pavement and furnish new aggregate base and subbase where there isn't existing pavement. The grades where there is existing pavement are not changing much at all and should require little to no additional aggregate base. New aggregate base and subbase are also to be utilized at the CMU entrance. Change the pay item Aggregate Base, 8 Inch to Aggregate Base, 8 inch, Modified. See the attached Bid Proposal.**
3. Add two directional arrows to indicate one-way traffic in the parking lot. The exact location is to be determined in the field. The following pay item is added to the attached Bid Proposal: **Pavt Mrkg, Ovly Cold Plastic, Thru Arrow Sym.**
4. Add one Do Not Enter sign at the west entrance to the main parking lot. The exact location is to be determined in the field. See the attached revised Special Provision. The pay item is added to the attached Bid Proposal: **Do Not Enter Sign.**
5. Change the size of the Stop sign from 24" to 30"x30" as shown on the attached revised Special Provision.
6. There is an additional tree to be removed on the south side of the west grouping of transformers. The quantity has been revised on the attached Bid Proposal.
7. Submit the attached Addendum #1 Proposal with your bid. Do not use the Proposal originally supplied with the bid documents.

City of Mt. Pleasant, Michigan
BID PROPOSAL
ADDENDUM #1

2013 MISSION STREET CONNECTOR ROAD #1

TO: City Hall/City Clerk
320 W. Broadway Street
Mt. Pleasant, MI 48858

BID DATE: July 16, 2013
TIME: 1:30 p.m.

The undersigned, as Bidder, hereby declares that his bid is made in good faith without fraud or collusion with any person or persons bidding on the same Contract; that he has carefully read and examined the Contract Documents, including the Notice to Bidders, Instructions, Bond Forms, Technical and Detailed Specifications, and Contract Drawings, for the designated work and understands all of the same; that he, or his representative, has made such a personal investigation at the site as is necessary to determine the character and difficulties attending the execution of the proposed work; and he proposes and agrees that if this Proposal is accepted, he will contract with the Owner in the form of the Contract hereto annexed, to provide necessary machinery, tools, apparatus and other means of construction, including utility and transportation services, necessary to do all the work and furnish all the materials and equipment specified or referred to in the Contract Documents, including Addenda No. __, __, and __, in the manner and time therein prescribed, and according to the requirements of the Owner as therein set forth to furnish Contractor Bonds and Insurance required of the Contractor by the Contract Documents, and that he will take in full payment therefore the unit prices set forth in the following Proposal.

The Bidder understands that the Owner reserves the right to reject any or all bids and to waive any irregularities in the bidding.

The Bidder agrees that his bid shall be good and may not be withdrawn for a period of sixty (60) calendar days after the scheduled closing time for receiving the bids.

Upon receipt of a written Notice of Award of the Bid, the Bidder shall execute the formal Contract Agreement attached hereto within ten (10) days and shall deliver to the Owner a Surety Bond or Bonds required. In the event the Contract and Bond are not executed within the time above set forth, the Bid Deposit attached in the sum of five percent (5%) of the Bid Proposal shall become the property of the Owner as liquidated damages for the delay and additional expense to the Owner caused thereby.

The Bidder hereby agrees to commence work under this Contract on or before date to be specified in the written Notice to Proceed executed by the Owner and to fully complete the project as stipulated in the Special Conditions. The Bidder further agrees to pay as liquidated damages the sum of Two Hundred Dollars (\$200.00) for each consecutive calendar day thereafter, as provided.

The below unit prices shall include all labor, materials, overhead, profit, insurance,

etc., to cover the finished work of the several kinds specified, and the Bidder agrees to perform all of the work described in the Specifications and/or shown on the Plans for the following unit prices:

CONNECTOR ROAD

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL COST
1	HMA Base Crushing and Shaping, Modified	2400	SYD	\$	\$
2	Excavation, Earth	60	CYD	\$	\$
3	Tree, Rem	1	EA	\$	\$
4	Stump, Rem	1	EA	\$	\$
5	Embankment, CIP	60	CYD	\$	\$
6	Curb and Gutter, Rem	240	FT	\$	\$
7	Sidewalk, Rem	35	SYD	\$	\$
8	Pavt, Rem	25	SYD	\$	\$
9	Subbase, CIP	45	CYD	\$	\$
10	Curb, Conc, Det E2	230	FT	\$	\$
11	Curb, Conc, Det F2	520	FT	\$	\$
12	Curb, Conc, Det F4	25	FT	\$	\$
13	Spillway, Conc	2	EA	\$	\$
14	Driveway, Opening, Conc, Det M	255	FT	\$	\$
15	Dr Structure, Repair	4	EA	\$	\$
16	Dr Structure Cover, CB, Modified	1	EA	\$	\$
17	Dr Structure Cover, Adj, Case 2	2	EA	\$	\$
18	Conc Pavt, Reinf, 6 inch	250	SYD	\$	\$
19	Sidewalk, Conc, 4 inch	220	SF	\$	\$
20	Sidewalk, Conc, Thickened Edge, 4 inch	550	SF	\$	\$
21	Decorative Colored Conc. Slab, 6 inch	580	SF	\$	\$
22	Sidewalk Ramp, Conc, 6 inch	100	SF	\$	\$
23	Detectable Warning Surface	10	FT	\$	\$
24	Expansion Jt, Backer Rod, Caulk	155	FT	\$	\$
25	HMA, 3C, Leveling Course (2 inch)	1820	SYD	\$	\$
26	HMA, 4C, Top Course (1.5 inch)	1820	SYD	\$	\$
27	Pavt Mrkg, Waterborne, 4 inch,	1	LS	\$	\$
28	Pavt Mrkg, Ovly Cold Plastic, Right Arrow	1	EA	\$	\$
29	Pavt Mrkg, Ovly Cold Plastic, 18 inch, Stop Bar	15	FT	\$	\$
30	Pavt Mrkg, Ovly Cold Plastic, Thru Arrow Sym.	2	EA	\$	\$
31	Stop Sign	1	EA	\$	\$
32	Right Turn Only Sign	1	EA	\$	\$
33	No Left Turn Sign	1	EA	\$	\$
34	Do Not Enter Sign	1	EA	\$	\$

35	Gate Box, Adj, Case 2	1	EA	\$	\$
36	Restoration, Modified	300	SYD	\$	\$
37	Dumpster Enclosure	1	LS	\$	\$
38	Minor Traffic Devices	1	LS	\$	\$
39	Testing (Allowance)	1	LS	\$ 2,500.00	\$ 2,500.00
40	Preconstruction Audio Video Recording	1	LS	\$	\$

SUBTOTAL \$

=====

(figures)

(written)

_____ and ____/100 Dollars

CMU APPROACH

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL COST
41	Excavation, Earth	155	CYD	\$	\$
42	Tree, Rem	19	EA	\$	\$
43	Stump, Rem	19	EA	\$	\$
44	Sidewalk, Rem	94	SYD	\$	\$
45	Subbase, CIP	75	CYD	\$	\$
46	Aggregate Base, 8 inch, Modified	207	SYD	\$	\$
47	Curb, Conc, Det F2	107	FT	\$	\$
48	Sewer, CI A, 12 inch, Tr Det B	6	FT	\$	\$
49	Sewer Tap, 12 inch	2	EA	\$	\$
50	Dr Structure Cover, CB, Modified	2	EA	\$	\$
51	Drop Inlet, Type 1	2	EA	\$	\$
52	Conc Pavt, Reinf, 6 inch (CMU 8' walk, w/ stone base)	54	SYD	\$	\$
53	Sidewalk, Conc, 4 inch	125	SF	\$	\$
54	Detectable Warning Surface	40	FT	\$	\$
55	HMA, 3C, Leveling Course (2 inch)	207	SYD	\$	\$
56	HMA, 4C, Top Course (1.5 inch)	207	SYD	\$	\$
57	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	105	FT	\$	\$
58	Pavt Mrkg, Ovly Cold Plastic, 18 inch, Stop Bar	18	FT	\$	\$
59	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Crosswalk	42	FT	\$	\$
60	Stop Sign	1	EA	\$	\$
61	Restoration, Modified	150	SYD	\$	\$
62	Minor Traffic Devices	1	LS	\$	\$
63	Testing (Allowance)	1	LS	\$ 300.00	\$ 300.00
64	Preconstruction Audio Video	1	LS	\$	\$

Recording				
-----------	--	--	--	--

SUBTOTAL \$

=====

(figures)

(written)

_____ and ____/100 Dollars

PAPA JOHN'S ENTRY AND PARKING

ITEM	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL COST
65	HMA Base Crushing and Shaping	500	SYD	\$	\$
66	Excavation, Earth	65	CYD	\$	\$
67	Embankment, CIP	40	CYD	\$	\$
68	Curb and Gutter, Rem	220	FT	\$	\$
69	Sidewalk, Rem	35	SYD	\$	\$
70	Pavt, Rem	10	SYD	\$	\$
71	Subbase, CIP	30	CYD	\$	\$
72	Aggregate Base, 8 inch, Modified	110	SYD	\$	\$
73	Curb, Conc, Det F2	160	FT	\$	\$
74	Curb, Conc, Det F4	10	FT	\$	\$
75	Driveway, Opening, Conc, Det M	100	FT	\$	\$
76	Sewer, CI A, 12 inch, Tr Det B	15	FT	\$	\$
77	Dr Structure Cover, CB, Modified	1	EA	\$	\$
78	Dr Structure Cover, Adj, Case 2	1	EA	\$	\$
79	Dr Structure, 36 inch dia	1	EA	\$	\$
80	Dr Structure, Tap, 12 inch	1	EA	\$	\$
81	Sidewalk, Conc, 4 inch	320	SF	\$	\$
82	HMA, 3C, Leveling Course (2 inch)	475	SYD	\$	\$
83	HMA, 4C, Top Course (1.5 inch)	475	SYD	\$	\$
84	Pavt Mrkg, Waterborne, 4 inch,	1	LS	\$	\$
85	Restoration, Modified	200	SYD	\$	\$
86	Minor Traffic Devices	1	LS	\$	\$
87	Testing (Allowance)	1	LS	\$ 750.00	\$ 750.00
88	Preconstruction Audio Video Recording	1	LS	\$	\$

SUBTOTAL \$

=====

(figures)

(written)

_____ and ____/100 Dollars

GRAND TOTAL BID

\$

=====

(figures)

(written)

_____ and ____/100 Dollars

The bid sections above are for accounting purposes only. The entire project will be awarded as one contract.

RESPECTFULLY SUBMITTED:

Company Name _____

Address _____

City _____ ST _____ Zip Code _____

Area Code/Telephone Number _____ Date _____

Fax _____

EMAIL _____

Authorized Signature _____

Print of Type Name and Title _____

EXPERIENCE QUESTIONNAIRE

To be furnished by Bidder
City of Mt. Pleasant, Michigan

The signatory of this proposal guarantees the truth and accuracy of all statements and of all answers hereinafter made.

1. How many years have you been in business as a contractor under your present name?

2. How many years have you been a principal officer of a firm under a different name?

Name of Firm _____

3. What projects of a similar nature has your organization contracted for within the past five years? (NOTE: Fill out each blank completely.)

Name of Owner & Location	Name/Address/Phone # of Person in Charge as Reference	Type of Work	Value of Work	Date Completed
--------------------------	---	--------------	---------------	----------------

1. _____

2. _____

3. _____

4. _____

City of Mt. Pleasant

SPECIAL PROVISION
FOR
SIGNAGE

City of MtPleasant

1 of 1

July 11, 2013

A) Description

This work consists of furnishing and installing signs and supports.

B) Materials

- 1) Stop sign.
 - i) Sign - 30"x30" Type III, Type C panel and face per Section 919.02 of the 2012 Standard Specifications for Construction.
 - ii) Support – Steel Post Sign Supports per Section 919.04.B of the 2012 Standard Specifications for Construction.
- 2) Right Turn Only sign.
 - i) Sign – 30"x36" R3-5 sign Type III, Type B panel and face per Section 919.02 of the 2012 Standard Specifications for Construction.
 - ii) Support – Steel Post Sign Supports per Section 919.04.B of the 2012 Standard Specifications for Construction.
- 3) No Left Turn sign.
 - i) Sign – 36"x36" R3-2 sign, Type III, Type B panel and face per Section 919.02 of the 2012 Standard Specifications for Construction.
 - ii) Support – Steel Post Sign Supports per Section 919.04.B of the 2012 Standard Specifications for Construction.
- 4) Do Not Enter sign.
 - i) Sign – 30"x30" R5-1 sign, Type III, Type B panel and face per section 919.02 of the 2012 Standard Specifications for Construction.
 - ii) Support – Steel Post Sign Supports per Section 919.04.B of the 2012 Standard Specifications for Construction.

C) Construction

- 1) All Signs
 - i) Install per Section 810.03 of the 2012 Standard Specifications for Construction.

D) Measurement and Payment

The complete work as measured for Signage will be paid for at the contract unit price for the following contract pay items and includes all material, equipment, and labor to complete these items.

- i) The unit price for all signs include the sign, support and footing (if required).

Contract Item (Pay Item)	Pay Unit
Stop Sign.....	Each
Right Turn Only Sign.....	Each
No Left Turn Sign.....	Each
Do Not Enter Sign	Each