

**2014 SEWER RELINING PROJECT
SPECIAL CONDITIONS**

SCOPE:

This project involves the relining of sanitary sewer mains in accordance with the specifications. All work required to complete the relining, reestablish the services, and return the main to full service shall be included in the unit prices in the proposal.

TIME CONSTRAINT:

The Contractor shall complete this work between May 5, 2014, and July 3, 2014. All work on this project shall be completed by July 3, 2014. Liquidated damages at the rate of \$300.00 per day will be assessed for each day the project is not completed beginning on July 3, 2014.

SCHEDULE:

The Contractor shall notify the City Inspector regarding their schedule for performing the work at least a week prior to the work beginning. The Contractor shall give the Water Supervisor a list of hydrants proposed to be used for the project prior to beginning any portion of the project. Upon completion of the project, the Contractor shall give the Water Supervisor a list of hydrants actually used during the project.

SEWER SERVICE:

The Contractor shall schedule all activities to minimize the impact of the sewer service interruption.

PIPE THICKNESS:

The minimum pipe thickness (manufactured nominal thickness) for the various pipes shall be:

- 8" CIPP – 6 mm
- 10" CIPP – 6.0 mm
- 12" CIPP – 7.5 mm
- 15" CIPP – 7.5 mm

STANDARD CONSTRUCTION SPECIFICATIONS:

The City of Mt. Pleasant's Standard Construction Specifications dated 2007 must be followed for construction on this project. They are available on the City's webpage at <http://www.mt-pleasant.org/docs/dept/engineering/genspec07.pdf>