



# THE CITY OF MT. PLEASANT, MICHIGAN

## CITY HALL

320 W. Broadway • 48858-2447  
(989) 779-5300  
(989) 773-4691 fax

## PUBLIC SAFETY

804 E. High • 48858-3595  
(989) 779-5100  
(989) 773-4020 fax

## PUBLIC WORKS

1303 N. Franklin • 48858-4682  
(989) 779-5400  
(989) 772-6250 fax

## PRE-BID ADDENDUM NO. 1

Project Bid: 2016 Southmoor Street Reconstruction

Bid Date: February 9, 2016  
Time: 1:30 p.m.

Opening: Office of the City Clerk  
City Hall  
320 West Broadway Street  
Mt. Pleasant, Michigan 48858

Addendum Issued By: Division of Public Works  
(989) 779-5401

Date Issued: January 22, 2016

Intent: Answer question regarding testing of the water main to be replaced—

For the east-west water main replacement, the contractor will need to install a valve, and run the new water main parallel to the old main with a blow off at one end. The old main will need to be active until testing of the new main is complete. At that time, the water services can be tied over to the new main, the new main can be tied in at the blow off end, and the old portion of the main abandoned. The contractor will be responsible for all cuts and caps required to properly install and test the new water main.

For the north-south water main replacement, a valve will need to be installed, the old main will be cut and capped. The new portion of the main will be installed with a blow off at one end. Once testing is complete, the new main can be connected to the existing main, and placed back into service.

Water main testing shall be in accordance with the City of Mt. Pleasant special provision.

Bid Proposal: See attached revised bid sheet.  
Added 1 valve, 2 water services and 2 cut and cap.

The below unit prices shall include all labor, materials, overhead, profit, insurance, etc., to cover the finished work of the several kinds specified, and the Bidder agrees to perform all of the work described in the Specifications and/or shown on the Plans for the following unit prices:

**BASE BID**

DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL COST
Preconstruction Audio/Video Recording	1	LS	\$	\$
Minor Traf Devices	1	LS	\$	\$
Drainage Structure, Rem	3	EA	\$	\$
Curb and Gutter, Rem	1,417	LFT	\$	\$
Pavt, Rem	2,513	SYD	\$	\$
Sidewalk, Rem	52	SYD	\$	\$
Sewer, Rem, Less Than 24 Inch	159	LFT	\$	\$
Machine Grading, Modified	7	STA	\$	\$
Subgrade Undercutting, Type II	25	CYD	\$	\$
Gas and Water Shutoff Cover Adj, Case 1	2	EA	\$	\$
Erosion Control, Filter Bag	3	EA	\$	\$
Dr Structure Cover, Adj, Case 1	1	EA	\$	\$
Dr Structure Cover, SAN, Modified	2	EA	\$	\$
Dr Structure, 48 inch dia	2	EA	\$	\$
Dr Structure Cover, STM, Modified	2	EA	\$	\$
Sewer, CI A, 6 inch, Tr Det B	600	LFT	\$	\$
Sewer, CI A, 8 inch, Tr Det B	32	LFT	\$	\$
HMA, 13A	150	TON	\$	\$
HMA, 36A	210	TON	\$	\$
HMA Approach	12	TON	\$	\$
Approach, CI I, 6 inch	85	SYD	\$	\$
Sidewalk Ramp, Conc, 6 inch	212	SFT	\$	\$
Sidewalk, Conc, 4 inch	225	SFT	\$	\$
Sidewalk, Conc, 6 inch	378	SFT	\$	\$
Detectable Warning Surface, Modified	24	FT	\$	\$
Subbase, CIP, Min. \$5.00	924	CYD	\$	\$

Underdrain, Subgrade, Open-Graded, 4 inch, Modified	1,406	FT	\$	\$
Aggregate Base, 8 Inch	2,266	SYD	\$	\$
Driveway, Nonreinf, Conc, 6 Inch	189	SYD	\$	\$
Driveway Opening, Conc, Det L	188	LFT	\$	\$
Curb and Gutter, Conc, Det F4, Modified	1,218	LFT	\$	\$
Restoration, Modified	7	STA	\$	\$
Relocate and Replace Mailbox (Inc. New Post)	8	EA	\$	\$
Water Main, Rem	253	LFT	\$	\$
Water Valve, Rem	2	EA	\$	\$
Water Main, 6 inch	253	LFT	\$	\$
Water Valve, 6 inch	2	EA	\$	\$
Connect to Existing Water Main	4	EA	\$	\$
Water Main, Cut & Cap	2	EA	\$	\$
Water Service	2	EA	\$	\$
Testing (Allowance)	1	LS	\$5,000	\$5,000
Contractor Staking	1	LS	\$	\$
<b>TOTAL</b>				<b>\$</b>

\_\_\_\_\_  
Total (written) \_\_\_\_\_ and \_\_\_\_/100 Dollars

RESPECTFULLY SUBMITTED:

Company Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ ST \_\_\_\_\_ Zip Code \_\_\_\_\_

Area Code/Telephone Number \_\_\_\_\_ Date \_\_\_\_\_

Fax \_\_\_\_\_

Email \_\_\_\_\_

Authorized Signature \_\_\_\_\_

Print of Type Name and Title \_\_\_\_\_